

STING

## WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

#### **SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-406**

CLIENT: Hilti 17 August 2020

P.O. Box 21148

Tulsa, Oklahoma 74121

TEST DATE: 29 July 2020

#### INTRODUCTION

The test was performed in accordance with ASTM E 90-09 (2016), Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and ASTM E2235-04 (2020), Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods.

Copies of the test standard are available at <a href="www.astm.org">www.astm.org</a>. The test chamber source and receiving room volumes are 204 and 148.4 cubic meters respectively. Western Electro-Acoustic Laboratory is accredited by the United States Department of Commerce, National Institute of Standards and Technology under the National Voluntary Accreditation Program (NVLAP) Lab Code 100256-0 for this test procedure. This test report relates only to the item(s) tested. This report must not be used to claim product certification, approval, or endorsement by WEAL, NVLAP, NIST or any agency of the federal government.

#### **DESCRIPTION OF TEST SPECIMEN**

The test specimen consisted of a double steel stud wall assembly with Type 'X' gypsum board installed on both sides of the panel, batt insulation in the stud cavity, and a total of four (4) steel pipes with an outer diameter (O.D.) of 59 mm (2-3/8 inch) installed in the center of the stud bays, one (1) pipe in each stud bay. A 13 mm (1/2 inch) joint was left around the pipe and was sealed with Hilti CS-S SA LIGHT Smoke and Acoustic sealant. Additional information regarding pipe installation provided in the details below.

#### **TEST CONFIGURATION**

Source Room Layers	Source Framing	Air Gap	Receiving Framing	Receiving Room Layers
1 layer 16 mm (5/8 inch) Type 'X' gypsum board	92 mm (3-5/8 inch) 25-gauge steel studs and 20-gauge slotted slip track spaced 610 mm (24 inches) on center with R-13 batt insulation in the cavity and Hilti CS-S SA LIGHT Smoke and Acoustic sealant at the 13 mm (1/2 inch) joint surrounding the steel pipes	25 mm (1 inch) with four (4) 59 mm (2-3/8 inch) O.D. steel pipes	92 mm (3-5/8 inch) 25-gauge steel studs and 20-gauge slotted slip track spaced 610 mm (24 inches) on center with R-13 batt insulation in the cavity and Hilti CS-S SA LIGHT Smoke and Acoustic sealant at the 13 mm (1/2 inch) joint surrounding the steel pipes	1 layer 16 mm (5/8 inch) Type 'X' gypsum board

- On both sides, the 92 mm (3-5/8 inch) 25-gauge steel studs were spaced 610 mm (24 inches) on center (O.C.) and were screwed to the 20-gauge slotted slip track with 12 mm (1/2 inch) truss screws. Unfaced R-13 fiberglass insulation was installed in the stud cavities. The frames were isolated from the test opening with 6 mm (1/4 inch) neoprene pads.
- On both sides, one layer of 16 mm (5/8 inch) Type 'X' gypsum board was screwed to the studs using 32 mm (1-1/4 inch) long #6 drywall screws spaced at 203 mm (8 inches) O.C. at the perimeter and 305 mm (12 inches) in the field.





STING

## WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

### **SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-406**

CLIENT: Hilti 17 August 2020

P.O. Box 21148

Tulsa, Oklahoma 74121

TEST DATE: 29 July 2020

- A total of four (4) steel pipes with an outer diameter (O.D.) of 59 mm (2-3/8 inch) were installed in the center of the stud bays, one (1) pipe in each stud bay. A 13 mm (1/2 inch) joint was left around the pipe and was sealed with Hilti CS-S SA LIGHT Smoke and Acoustic sealant. The pipes were installed using plumber's tape metal strapping looped around the pipe to suspend it in the center of the stud bay. 6 mm (1/4 inch) felt was used to isolate the pipe from the strapping. The pipe was packed with mineral wool insulation, capped on each side, and extended a total of 102 mm (4 inches) past the face of the gypsum board. See photos for conditions.
- All gypsum board was oriented vertically with joints staggered on opposite sides. Aside from the four (4) pipe joints, the remaining gypsum board joints were sealed with a bead of latex caulking and metal foil tape. All screw heads were covered with metal foil tape.
- The overall dimensions of the wall assembly were 2.44 m (96 inches) wide by 2.44 m (96 inches) high by 241 mm (9-1/2 inches) thick.
- The overall weight of the assembly was estimated to be 170.3 kg (375.5 lbs.) for a calculated surface density of 28.8 kg/m<sup>2</sup> (5.9 lbs./ft<sup>2</sup>).

#### **RESULTS OF THE MEASUREMENTS**

One-third octave band sound transmission loss values are plotted and tabulated on the attached sheet. ASTM minimum volume requirements are met at 80 Hz and above. The Outdoor-Indoor Transmission Class rating determined in accordance with ASTM E 1332-10a was OITC 48. The Sound Transmission Class rating determined in accordance with ASTM E 413-10 was STC 65.

Approved:

Stephen A. Martin, Ph.D., P.E

**Laboratory Director** 

Respectfully submitted,
Western Electro-Acoustic Laboratory

Raul Martinez

Acoustical Test Technician





STING

# **WESTERN ELECTRO - ACOUSTIC LABORATORY**

CALIBRATION •

RESEARCH


25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

## **SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-406**

CLIENT: Hilti 17 August 2020

P.O. Box 21148

Tulsa, Oklahoma 74121



1/3 OCT BAND CNTR FREQ		63	80	100	125	160	200	250	315	400	500
TL in dB		21	32	35	41	46	50*	55*	57*	62*	66*
95% Confidence in dB		1.42	1.92	2.07	1.47	0.89	0.76	0.80	0.52	0.36	0.38
deficiencies					(8)	(6)	(5)	(3)	(4)	(2)	
1/3 OCT BAND CNTR FREQ		630	800	1000	1250	1600	2000	2500	3150	4000	5000
TL in dB		70*	73*	76*	75*	74*	68	72*	69	66	64
95% Confidence in dB		0.29	0.44	0.38	0.39	0.36	0.56	0.55	0.31	0.32	0.50
deficiencies							(1)		(0)	(3)	
EWR	OITC	* Minimum estimate of	1 Cot Bato. 20 Gary 2020								STC
64	48	transmission loss. Measurement limited by	Specimen Area: 64 sq.ft.								65
filler wall.  Actual TL will be equal or greater than value reported.			Tempe	rature:	78.8 deg. F						(32)
		Rela	itive Hu	midity:	37 %						





# **WESTERN ELECTRO - ACOUSTIC LABORATORY**

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

## **SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-406**

CLIENT: Hilti 17 August 2020

P.O. Box 21148

Tulsa, Oklahoma 74121

TEST DATE: 29 July 2020

### PHOTO(S) OF TEST SPECIMEN







TESTING

# **WESTERN ELECTRO - ACOUSTIC LABORATORY**

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

### **SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-406**

CLIENT: Hilti 17 August 2020

P.O. Box 21148

Tulsa, Oklahoma 74121







TESTING

# **WESTERN ELECTRO - ACOUSTIC LABORATORY**

CALIBRATION • RESEARCH


25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

### **SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-406**

CLIENT: Hilti 17 August 2020

P.O. Box 21148

Tulsa, Oklahoma 74121







# **WESTERN ELECTRO - ACOUSTIC LABORATORY**

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

## **SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-406**

CLIENT: Hilti 17 August 2020

P.O. Box 21148

Tulsa, Oklahoma 74121



