

STING

WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

SOUND TRANSMISSION LOSS TEST REPORT NO. TL22-220

CLIENT: Hilti

7250 Dallas Parkway, Suite 1000 7 December 2022

Plano, Texas 75024

TEST DATE: 14 November 2022

INTRODUCTION

The test was performed in accordance with ASTM E 90-09 (2016), Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and ASTM E2235-04 (2020), Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods. Copies of the test standard are available at www.astm.org. The test chamber source and receiving room volumes are 204 and 148.4 cubic meters respectively. Western Electro-Acoustic Laboratory is accredited by the United States Department of Commerce, National Institute of Standards and Technology under the National Voluntary Accreditation Program (NVLAP) Lab Code 100256-0 for this test procedure. This test report relates only to the item(s) tested. This report must not be used to claim product certification, approval, or endorsement by WEAL, NVLAP, NIST or any agency of the U.S. government.

DESCRIPTION OF TEST SPECIMEN

The test specimen was a double steel stud wall assembly with type 'x' gypsum board and R-13 fiberglass batt insulation and Hilti CFS-BTS bottom track seal.

Specimen Make-up (So	urce to Receive)									
Layer 1	16 mm (5/8 inch) type 'x' gypsum board									
Layer 2	16 mm (5/8 inch) type 'x' gypsum board									
Framing and Insulation	64 mm (2-1/2 inch) 33mil steel studs spaced 610 mm (24 inches) on center (o.c.) with R-13									
Framing and insulation	fiberglass batt insulation in the cavity									
Air Space	25 mm (1 inch)									
Framing and Insulation	64 mm (2-1/2 inch) 33mil steel studs spaced 610 mm (24 inches) on center (o.c.) with R-13									
Training and insulation	fiberglass batt insulation in the cavity									
Layer 3	16 mm (5/8 inch) type 'x' gypsum board									
Layer 4	16 mm (5/8 inch) type 'x' gypsum board									
Installation Information										
Layer Installation	- Layers 1 and 4: 41 mm (1-5/8 inch) long #6 drywall screws spaced 203 mm (8 inches)									
	o.c. at the perimeter and 305 mm (12 inches) o.c. in the field									
	- Layers 2 and 3: 32 mm (1-1/4 inch) long #6 drywall screws spaced 203 mm (8 inches)									
	o.c. at the perimeter and 305 mm (12 inches) o.c. in the field									
	- All gypsum board was oriented vertically with joints staggered on opposite sides of									
	the wall									
	- All joints and perimeters were sealed with a bead of caulking and metal foil tape									
Framing and Insulation	- Studs were spaced 610 mm (24 inches) o.c.									
Installation	- Studs were secured to the track using 51 mm (1/2 inch) pan-head truss screws.									
	- The frame was isolated from the test chamber opening via neoprene pucks.									
	- Full cavity R-13 fiberglass insulation was installed in the stud cavities.									
Other	- A 16 mm (5/8 inch) gap was left at the bottom joint on both sides of the wall									
	assembly and was filled with the Hilti CFS-BTS bottom track seal.									
	- On both sides, the joint was filled with the 32 mm (1-1/4 inch) thick product.									
	- The product was installed per manufacturer's instructions by adhering the product to									
	the stud track and compressing the gypsum board against the top, outer portion.									

Page 1 of 4

TESTING



WESTERN ELECTRO - ACOUSTIC LABORATORY

TESTING • CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

SOUND TRANSMISSION LOSS TEST REPORT NO. TL22-220

CLIENT: Hilti

7250 Dallas Parkway, Suite 1000 7 December 2022

Plano, Texas 75024

TEST DATE: 14 November 2022

- The overall dimensions of the specimen were 2.44 m (96 inches) wide by 2.44 m (96 inches) high by 216 mm (8-1/2 inches) thick.
- The overall weight of the assembly was estimated to be 283.2 kg (624 lbs) for a calculated surface density of 47.6 kg/m² (9.76 lbs./ft²).

RESULTS OF THE MEASUREMENTS

One-third octave band sound transmission loss values are plotted and tabulated on the attached sheet. ASTM minimum volume requirements are met at 80 Hz and above. Please note the 95% confidence intervals presented in the transmission loss plot refers to the spatial uniformity and sampling uncertainties of the measurement system only. It does not represent the overall repeatability or reproducibility of the test method as defined in Section 13 of ASTM E 90-09 (2016).

The Outdoor-Indoor Transmission Class rating determined in accordance with ASTM E 1332-10a was OITC-50. The Sound Transmission Class rating determined in accordance with ASTM E 413-10 was STC-63.

Respectfully submitted,

Approved:

Western Electro-Acoustic Laboratory

Stephen A. Martin, Ph.D., P.E.

Laboratory Director

Chris Kezon Quality Manage



STING

WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION

RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

SOUND TRANSMISSION LOSS TEST REPORT NO. TL22-220


CLIENT: Hilti

7250 Dallas Parkway, Suite 1000

7 December 2022

Plano, Texas 75024

TEST DATE: 14 November 2022



1/3 OCT BAND CNTR FREQ			63	80	100	125	160	200	250	315	400	500
TL in dB			31*	39*	39	39	46	50	55	58*	62*	65*
95% Confidence in dB		1.42	1.92	2.07	1.47	0.89	0.76	0.80	0.52	0.36	0.38	
deficiencies						(8)	(4)	(3)	(1)	(1)	(0)	
1/3 OCT BAND CNTR FREQ		630	800	1000	1250	1600	2000	2500	3150	4000	5000	
TL in dB		66	65	63	68	69	65	66	71	74	75	
95% Confidence in dB		0.29	0.44	0.38	0.39	0.36	0.56	0.55	0.31	0.32	0.50	
deficiencies * Minimum estimate of			(0)	(3)			(2)	(1)				
EWR	OITC	transmission loss. Measurement limited by filler wall. Actual TL will be equal or	Test Date: 14 November 2022									STC
63	50		Specimen Area: 64 sq.ft.									63
	greater than value reported.			Temperature: 72.3 deg. F							(23)	
		reported.	Relative Humidity: 33 %									

Report must be distributed in its entirety except with written permission from Western Electro-Acoustic Laboratory





WESTERN ELECTRO - ACOUSTIC LABORATORY

TESTING • CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

SOUND TRANSMISSION LOSS TEST REPORT NO. TL22-220

CLIENT: Hilti

7250 Dallas Parkway, Suite 1000 7 December 2022

Plano, Texas 75024

TEST DATE: 14 November 2022

PHOTO OF TEST SPECIMEN



NVLAP LAB CODE 100256