


No.	Unit Qty	Unit	Description	Box Qty	# Boxes Needed	Item No.	Torque ft - Ibs
1	AS REQ'D	EA	STRUT HS-158-12/HDG 10'	1	AS REQD	407570	-
2	4	EA	CHANNEL END CAP MEK RED	50	1	244886	16
3	2	EA	MQV-UB-M12 (#304884)	10	1	SPECIAL	
4	2	EA	USE KB-TZ SS AS APPROPRIATE	VARIES	VARIES	VARIES	40
5	2	EA	WING NUT MQM-F3/8"-F	25	1	304136	
6	2	EA	HEX HEAD BOLT 3/8" x 1-1/4" SS316	50	1	411788	30
7	2	EA	WASHER 3/8" SS316	200	1	411780	-
8	2	EA	BASE PLATE MQZ-F1/2"-F	20	1	304201	-
9	1	EA	U-BOLT	VARIES	VARIES	SPECIAL	-





NOTE(S):

- 1. PRELIMINARY NOT FOR CONSTRUCTION
- 2. DESIGN ASSUMPTIONS:
 - a. DESIGN LOADS (STATIC, U.N.O.):

DEAD LOAD (VERTICAL) = 200lb.

LATERAL LOADS

PARALLEL TO PIPE = 50lb.

PERPENDICULAR TO PIPE = 0lb.

- b. LATERAL LOADS ARE WIND OR SEISMIC PER GOVERNING CODE.
- c. LATERAL LOADS APPLIED AT THE SAME TIME AS DEAD LOAD.
- d. BUILDING CODE: NOT SPECIFIED
- e. CORROSION RESISTANCE REQD.: HDG
- ALL LOADS ASSUMED TO ACT AT CENTER OF PIPE(S), U.N.O.
- 4. REFER TO COMPONENT MANUFACTURER'S IFUS FOR REQUIRED INSTALLATION INFO.
- 5. E.O.R. MUST BE NOTIFIED OF ANY DEVIATIONS FROM EXISTING/ NEW SUBSTRATE CONDITIONS SHOWN HEREIN TO VALIDATE ACCEPTANCE OF THIS HILTI DESIGN PRIOR TO INSTALLATION.
- 6. MAX. 1 PIPE PER SUPPORT.
- 7. ATTACHMENT TO BASE MATERIAL ARE CONCEPTUAL ONLY. ATTACHMENT SHALL BE DESIGNED BY THE ENGINEER OF RECORD.



All loading and design criteria supplied by customer is assumed accurate. Only the stated Design Assumptions were considered, and must be verified by the responsible Engineer of Record (EOR). The basis of Hilti component and connection design is the published data in the current Hilti Technical Guide, including material and cross-section properties, allowable load values, factors of safety, methods of calculation, and limiting factors. The EOR must verify suitability for any specific application, and the capacity of the supportive structure to receive the shown configuration and associated reaction loads. Modification to components and/or design may alter performance and must be evaluated by the EOR

TYPICAL DETAIL TYPE:

PIPE SUPPORT

TYPICAL DETAIL DESCRIPTION:

POST

DESIGNED BY:	REVIEWED BY:	
KL	AJV	
DRAWN BY:	ISSUE DATE:	
НАМ	10 DEC 14	

RE	VIS	101	NS:

NO:	DESCRIPTION:	DATE:
<u>A</u>	ORIGINAL ISSUE	10 DEC 14
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		
_		

TYPICAL DETAIL NOMENCLATURE:

P-P53-C

DRAWING NUMBER:	SHEET:		
01	1/1		